



NOTES:

1. THE CONTRACTOR SHALL COORDINATE WITH THE CITY OF WADSWORTH TO SHUT DOWN THE WATER MAIN. ALL RESIDENTIAL CUSTOMERS AFFECTED BY THE PROPOSED WORK SHALL BE NOTIFIED AT LEAST 24 HOURS PRIOR TO SHUT DOWN AND ALL COMMERCIAL PROPERTIES SHALL BE GIVEN 7 DAYS NOTICE.
2. ALL RELOCATED WATERLINES SHALL BE INSTALLED TO THE NEW LINE GRADE, TESTED AND DISINFECTED PRIOR TO SHUT DOWN OF THE EX. MAIN AND CONNECTION OF THE RELOCATED LINES TO THE EX. MAIN.
3. IF DEPTH OR LENGTH OF PIPE BETWEEN BENDS REQUIRES A JOINT, FIELD-LOK GASKETS SHALL BE INSTALLED AT ALL JOINTS.
4. FOR WATERLINE LOWERING IN NEW CONSTRUCTION, FULL LENGTHS OF PIPE SHALL BE INSTALL OUT OF STA. "A" AND "D".
5. IF ALL-THREAD IS USED FOR RESTRAINED JOINTS, IT SHALL BE STAINLESS STEEL AND IN ACCORDANCE WITH NFPA 10.8.3.1.2.